

CFB-FGD for 660MW Coal-fired Units

Introduction of Hanfeng Project



Lonjing Environment Technology

Dr. Jianchun Wang

Content

- Background
 - Design
 - Construction
 - Commissioning
 - Operation
 - By-product utilization
-

Background

Project : Hanfeng 2X660MW Power Plant FGD Retrofit Project

Boiler: 2 boilers, 660MW each, FW supply, Peak load operation.

Fuel: Anthracite + lean coal, 1.5% sulfur content.

Conditions:

- Low space available
- Water shortage region
- Short outage time required

CFB-FGD system from Longking was adopted

Content

- Background
 - Design
 - Construction
 - Commissioning
 - Operation
 - By-product utilization
-

Design

Item	Unit	Value
Flue gas temperature (inlet)	°C	135
Flue gas flow rate (inlet)	Nm ³ /h	2,550,000
SO ₂ concentration (inlet)	mg/Nm ³ (STD, 6%O ₂)	3200
Dust concentration (inlet)	mg/Nm ³	1000
DeSOx efficiency	%	≥90
SO ₂ concentration (outlet)	mg/Nm ³ (STD, 6%O ₂)	≤200
Dust concentration (outlet)	mg/Nm ³	≤30

Design




Physical modeling of flue path to improve and verify the design

Introduction of Hanfeng Project

Design

Layout Drawing



Content

- Background
 - Design
 - Construction
 - Commissioning
 - Operation
 - By-product utilization
-

Construction



Transport/Package



Introduction of Hanfeng Project

Construction


The construction progress 1



Introduction of Hanfeng Project

Construction

The construction progress 2



Introduction of Hanfeng Project

Construction


The end of construction (Oct. 2008)



Content

- Background
 - Design
 - Construction
 - Commissioning
 - Operation
 - By-product utilization
-

Commissioning



Commissioning

13th Dec. 2008, unit 2# went through 168h commissioning.

31th Dec. 2008, unit 1# went through 168h commissioning.

EPC project, 11 months in total



Content

- Background
 - Design
 - Construction
 - Commissioning
 - Operation
 - By-product utilization
-

Operation

Performance Acceptance Certification

监测报告

(三) 监测结果

1、1#机组脱硫系统

A 岛脱硫系统出口烟尘排放浓度为 $23\sim27 \text{ mg/m}^3$, 除尘效率为 95.07~96.13%; 二氧化硫排放浓度为 $123\sim150 \text{ mg/m}^3$, 脱硫效率为 92.51~93.60%; 氮氧化物排放浓度为 $774\sim823 \text{ mg/m}^3$ 。

B 岛脱硫系统出口烟尘排放浓度为 $19\sim28 \text{ mg/m}^3$, 除尘效率为 93.79~97.07%; 二氧化硫排放浓度为 $114\sim135 \text{ mg/m}^3$, 脱硫效率为 92.93~93.79%; 氮氧化物排放浓度为 $795\sim819 \text{ mg/m}^3$ 。

以上监测结果均达到《火电厂大气污染物排放标准》(GB13223-2003)
I 时段相应标准限值要求, 为达标排放。

项目名称: 邯峰发电厂 2#机组脱硫工程
建设单位: 河北邯峰发电有限责任公司

河北省环境监测中心站
二〇〇八年十二月十五日

Operation

Performance Acceptance Certification Data

序号	项目名称	单位	设计		实际运行	
			1#炉	2#炉	1#炉	2#炉
1	机组大小	MW	660		660	
2	设备可用率	%	97		98	
3	脱硫入口烟气量	万Nm ³ /h	255		229.9	223.6
4	脱硫入口烟气温度	℃	135		122.7	124.3
5	脱硫入口含尘量	mg/Nm ³	200		764	729.9
6	脱硫入口SO ₂ 浓度	mg/Nm ³	3200		2741.4	2434.2
7	脱硫出口烟气温度	℃	70		71.7	72.5
8	脱硫出口含尘量	mg/Nm ³	50		8.5	8.2
9	脱硫出口SO ₂ 浓度	mg/Nm ³	400		190.7	133.5
10	脱硫效率	%	90		93.04	94.52
11	石灰消耗量	t/h	9.6		9.58	9.76
12	水消耗量	t/h	101.4		82.98	82.65
13	脱硫系统电耗	kW	8600		7946.5	7819

Content

- Background
 - Design
 - Construction
 - Commissioning
 - Operation
 - By-product utilization
-

By-product utilization





Introduction of Hanfeng Project

By-product utilization

检验报告

NO. ZP09-479

样品名称 脱硫灰标准砖

委托单位 福建海源自动化机械股份有限公司

受检单位 福建海源自动化机械股份有限公司

报告日期 2009.9.7

福建省建筑材料质量监督检验站

地址：福州市杨桥中路174号 邮政编码：350002
电话：(0591)83774864 传真：(0591)83774864

MA CNAS 检测 No.CNAS L1303 2007年质监认字第002号

福建省建筑材料质量监督检验站

检验报告

编号: ZP09-479
第1页共2页

任务来源	福建海源自动化机械股份有限公司	检测类别	委托检验
委托	福建海源自动化机械股份有限公司	样品名称	脱硫灰标准砖
地址	福州市闽侯县工业集中区	商标	/
时间	350101	型号规格	MU150.0 240×115×53
电话	/	等级	/
传真	/	出厂编号	/
生产单位	福建海源自动化机械股份有限公司	生产日期	/
日期	/	抽样单位	/
地点	/	抽样承检	/
方法	/	抽样数量	/
样品	20块	抽样日期	2009年9月1日
概况	说明 样品状况良好，符合试验条件要求		
检验依据	JC239-2001《烧结灰砖》		
检验项目	外观质量、尺寸偏差、抗压强度、抗折强度、吸水率、密度等项		
检验结果	(详见结论)		
检验结论	所检项目外观质量、尺寸偏差、抗压强度和抗折强度符合 JC239-2001 标准中 MU150.0 等级技术要求。吸水率和抗压强度无指标要求。本报告仅作此检验结果。		
说明	/		
报告日期	2009.9.1~2009.9.7		

经办人: **王红印** 审核人: **林日初** 批准人: **林光华**

福建省建筑材料质量监督检验站

检验报告

编号: ZP09-479
第2页共2页

尺寸	检测项目	单位	技术要求 (MEE 20.0)	检验结果	单块 评定
偏差	长度	mm	±4	20块样品: -2~-3.0	合格
	宽度	mm	±3	20块样品: 0~-2	
	对应高度差	mm	≤3	20块样品: 2	
外观	缺棱掉角	mm	最小缺棱尺寸≤20	合格	
	完平面	/	不少于一条面和一项面		
	平整度	mm	大面积: 垂直方向长≤70 其它部位≤100		
	层型	mm	不允许		
质量	抗压强度	MPa	平均值≥20.0 单块最小值≥16.0	平均值: 21.1 单块最小值: 18.7	合格
	抗折强度	MPa	平均值≥4.0 单块最小值≥3.2	平均值: 6.4 单块最小值: 5.8	
	吸水率	%	/	8.2	
	密度等级	kg/m ³	/	1504	

Thank you
